

JD- Technician for City Gas Distribution

Organization Name	North Star Techno Services Pvt. Ltd.
Company URL	www.nstspl.in
Industry Type	Petroleum and Natural Gas: CGD (City Gas Distribution) Pipeline Network
Designation / Job Profile	Technician-MDPE/GI
No. of Positions / Vacancies	Total Current Requirement: 100 <ul style="list-style-type: none"> ✓ Delhi- 20 ✓ Dharwad (Karnataka)-20 ✓ Rewa & Gwalior (M.P)- 30 ✓ Samastipur, Chapra & Purnia (Bihar) - 30
Qualification Required	ITI in Plumber/Fitter Trade or 8 th /10 th / 12 th passed + skilled in plumbing fitter fabrication, electrician or any other technical trade with Vision India
Experience	Both Fresher & Experience (0 to 1 Year)
Age Limit	18-25 Years (As per 10th Certificate / Aadhar Card)
Nature of the Job	Laying any type of CGD (City Gas Distribution) Pipeline Network & PNG for Household, Commercial & Industrial (Gas Pipe Lines)
Job Profile :-	<ul style="list-style-type: none"> • Technician have knowledge of Gas pipe (GI) fitting knowledge 1/2, 3/4, 1, 1.5, 2 inches pipe. Installation of GI fittings like elbows, tees, unions, sockets, reducers, GI plugs, any other GI fittings, adopter for appliance valves & Anaconda, Domestic Adaptor, GI Sleeves, RCC Crimping Guard, Meter clamp & Pipe clamps etc. as required to complete the job. • Drilling of holes through walls with proper heavy duty hammer drill Machine, tools & tackles, using proper sealant/ grout material & color to match original, replacement of damages during drilling, restoring the area to original condition to the satisfaction of Owner/ EIC & as per specification for 1/2" & 1" NB in brick wall and RCC wall. PVC sleeve with proper sealant to be provided in the drilled section to protect GI pipe. • Installation of powder coated GI riser of 1" & 1/2" from TF to Riser Isolation Valve, from Riser Isolation Valve up to lateral Isolation Valve by providing plug at all levels up to all floors including supply and fixing of all type of pipe supports/ clamps/ brackets. • Installation of 1/2" Powder Coated GI pipe & Fittings at all length up to appliance valve/gas tap at domestic household for connecting PNG

	<p>connection with GI Riser network with end cap/ plug (included).</p> <ul style="list-style-type: none"> • Connection ready for commissioning (RFC) by installation of lateral isolation valve (included) at all length after lateral isolation valve along with installation of regulator, meter with associated inlet & outlet connections/ fittings/ anaconda, supply and fixing of approved meter brackets and other supports up to appliance valve (excluded). • Conversion of all types of LPG kitchen appliances to PNG based appliances by installing appliance valve, suraksha hose of 1 meter, changing/ converting nozzles, jets and associated controls for domestic & imported appliances with proper tools & tackles. • Measurement of pipeline and Drawing of the work. • Inventory confirmation and utilization report to respective supervisor
OJT Period (Training Period / Nesting Period)	6 Months
Working Hours (Shift Timings)	Applicable as per Normal Working Hours
Any Other requirement of Employer in terms of Traits / Any Other Specific Remarks	Go getter, high on need and positive attitude
Salary CTC	15000 CTC
Incentives (Yes / No) if yes, how much	Yes. Will be communicate time to time- Project Based
Confirmation Period	6 Months
PF / ESI Deduction (Yes / No)	Yes. Post confirmation (Not during training period)